

**Old Murray Middle School Demolition Project
Existing Condition Photos
d. Hall, 5/29/18**

Scope of Work, item #3: MJH52 Track & Football Field



MJH52 – west end track, remove curb, bf/compact



MHJ52 – remove concrete structures, footings, bf/compact



MJH52 – remove fence, structures & footings, bf/compact



MJH52 – remove irrig box, cap lines, bf/compact (typ)



Remove MMS perimeter fence, posts, bf/compact



MJH52 – remove concrete vault, cap lines, bf/compact



MJH52 – remove valve & box, cap line, bf/compact (typ)



MJH52 – backflow device, cover, vault, lines & valves to remain



MJH52 – backflow device, cover, vault, line service to remain



MJH52 – remove goal posts, lights & poles, bf/compact

MJH52 – remove discus/shot-put slab, bf/compact



MJH52 – remove broad jump, bf/compact

MJH52 – Track & Football field: import clean fill dirt, smooth finish grade; no ponding in finish grade



MJH52 – remove lights & poles, bf/compact, irrigation boxes, valves, cap lines; import clean fill dirt, smooth finish grade football field & track area; no ponding in finish grade



Old Murray Middle School
Sierra Sands Unified School District

Page 4 of 9

photos, existing condition
NAWS

MJH 55 – remove MMS perimeter fence, posts, bf/compact (slab & riser to remain)



MJH55 – remove backstop, fence, posts, bf/compact

MJH 55 – soft ball field east, remove fence, backstop, posts, bf/compact



MJH55 – remove dugout pits, cap water line, remove riser, bf/compact



MJH55 – remove home plate, pitching mound & base anchors



MJH55 – remove softball field line fence, posts, bf/compact; import clean fill dirt, smooth finish grade entire softball field east; no ponding in finish grade



MJH56 softball field west – remove concrete slab, retaining wall, footing & wood pole, bf/compact





MJH56 – remove concrete slab, retaining wall, footing, wood pole, gymnastic pipes & footings, bf/compact



MJH56 – remove signage poles, footings, gymnastic pipes, footings, bf/compact; import clean fill dirt, smooth finish grade entire softball field west, no ponding



MJH54 – demolish & remove from site metal building, SOG, footings, cut & cap water, sewer & gas 5' from building; remove power pole, bf/compact; import clean fill dirt, smooth finish grade area with adjacent area of MJH 52 (track & field); no ponding in finish grade



MJH54 – demolish metal & wood building; remove wood power pole; remove abandoned power line back to MJHPE building & disconnect at electrical panel; C.L. fence & basketball court to remain; smooth finish grade, no ponding



MJH 50 & MJH53 – demolish ball wall, building, stem wall & concrete footing, bf/compact; saw cut existing asphalt pavement adjacent to C.L. fence at basketball court; pulverized asphalt and smooth finish grade; import clean fill dirt as needed for smooth finish grade where MJH 50, MJH52, MJH53, MJH54, MJH55 & MJH56; no ponding in finish grade



MJH50 – saw cut asphalt pavement adjacent to C.L. fence at basketball court; pulverize asphalt



MJH58 – West Play Field (basketball/tetherball) pulverize asphalt court at west end of campus; remove goal posts & tether ball poles; bf/compact; import clean fill dirt; smooth finish grade; no ponding



MJH58 – remove concrete apron out to road; remove MMS perimeter fence; pulverize asphalt court; import clean fill dirt; smooth finish grade; no ponding



MJH58 – pulverize asphalt court and smooth grade; remove concrete structure & bench; import clean fill dirt; smooth finish grade; no ponding



MJH58 – water meter to remain; protect in place



MJH33 – demolish & remove temporary pipe shelter